


FIRST FLOOR PLAN -EXISTING
 MECH. DEMOLITION
 SCALE: 1/8"=1'-0"



◇ SHEET NOTES

- ◇ 1 REMOVE ALL EXIST. DUCT UNLESS NOTED OTHERWISE.
- ◇ 2 REMOVE EXISTING DUCTWORK UNDER STAGE
- ◇ 3 EXISTING CABINET HEATER TO REMAIN
- ◇ 4 REMOVE EXISTING EXH. DUCT COMPLETE.
- ◇ 5 NO WORK THIS ROOM
- ◇ 6 EXISTING PLUMBING FIXTURE TO REMAIN. CONTRACTOR TO CHECK FIXTURE FOR CORRECT OPERATION AND REPAIR IF NECESSARY.
- ◇ 7 EXISTING LAV. TO BE REMOVED. NEW LAV. TO TO BE INSTALLED, SEE PLUMBING DRAWINGS.
- ◇ 8 EXISTING KITCHENETTE TO BE RELOCATED. CAP ALL PIPING BELOW AND BEHIND WALL AND FLOOR.
- ◇ 9 EXISTING HVAC UNITS AND DUCTWORK TO BE REUSED. SEE SHEET M-2 FOR WORK PERTAINING TO THESE SYSTEMS.
- ◇ 10 EXISTING WINDOW UNIT TO REMAIN

NATIONAL COLLEGE

of BUSINESS & TECHNOLOGY

PROPOSED REFURBISHING & REMODELING

115 EAST LEXINGTON AVE.
 DANVILLE, KY.



GENERAL CONTRACTORS
 CONSTRUCTION MANAGERS

331 Boxley Avenue
 Louisville, Kentucky 40209

FIRST FLOOR
 PLAN-EXISTING
 MECH. DEMOLITION

DRAWN BY	DATE	DWG. NO.
JEH	06/09/04	9402-Dm2
REVISIONS		

JEH 06/09/04 9402-Dm2

REVISIONS

Dm2