


SECOND FLOOR PLAN - EXISTING
DEMOLITION
SCALE: 1/8" = 1'-0"



SHEET NOTES

- UNLESS NOTED OR INDICATED TO BE REMOVED ON THE PLAN, EXIST. FINISHES AND ELEMENTS SHALL REMAIN AS THEY EXIST. FINISHES AND ELEMENTS TO REMAIN SHALL BE PROTECTED FROM SOIL OR DAMAGE, IF SOILED OR DAMAGED, THEY SHALL BE REPAIRED TO THE OWNER'S SATISFACTION AT THE EXPENSE OF THE CONTRACTOR PRODUCING THE CONDITIONS TO BE REPAIRED.
- ① CARPET, BASE AND EDGE TRIM TO BE REMOVED BY THE HAZARDOUS MATERIAL ABATEMENT CONTRACTOR UNDER SEPARATE CONTRACT.
 - ② NEW ELEVATOR FLOOR OPENING - SEE PLANS SHT. A5 SAW CUT EDGES AND REMOVE EXIST. CONC. & METAL FIRST FLOOR DECK AND BASEMENT PLAS. & MET. LATH CLG. TO REMOVE EXIST. STEEL JOIST AND PROVIDE CLEARANCE FOR NEW CONSTR./SEE ELEVATOR AREA LAYOUT SHT. A5/COORD. OPNG. SIZE WITH ELEV. CONTR.
 - ③ REMOVE RESIL. WALL BASE FROM AREA TO RECV. NEW FLOOR FINISH AND PREPARE WALL TO RECV. NEW BASE/COORD. WITH THE ROOM FINISH SCHED.
 - ④ EXIST. FLOOR TILE TO REMAIN BELOW NEW FLOOR FINISH/SEE PLAN SHT. A1 AND ROOM FINISH SCHED.
 - ⑤ INSTALL DOOR, CASING, AND HARDWARE IN NEW OPNG./SEE REMODELLING PLAN SHT. A3
 - ⑥ HAZARDOUS MATERIAL ABATEMENT CONTRACTOR TO REMOVE 12" SQ. AREAS OF ACoust. PLASTER COATING AT 4'-0" O.C. NORTH-SOUTH AND EAST-WEST FOR INSTALLATION OF NEW CLG. HANGERS/NEW CLG. CONTR. TO COORD. EXACT LOCATIONS DURING CONSTRUCTION.

NATIONAL COLLEGE

of BUSINESS & TECHNOLOGY

PROPOSED REFURBISHING & REMODELING

115 EAST LEXINGTON AVE.
DANVILLE, KY.



GENERAL CONTRACTORS
CONSTRUCTION MANAGERS

331 Boxley Avenue
Louisville, Kentucky 40209

SECOND FLOOR PLAN - EXISTING
DEMOLITION

DRAWN BY	DATE	DWG. NO.
RLH	06/09/04	9402-D3

REVISIONS	

LEGEND

- ==== EXIST. WALL OR PARTITION TO BE REMOVED /COORD. WITH NEW CONSTR.-SEE REMODELING PLAN
- - - - EXIST. DOOR AND HARDWARE TO BE REMOVED/REMOVE CASING & TRIM AT OPNGS. TO BE CLOSE ONLY-SEE REMODELING PLAN
- ||| CONSTR. NEW OPNG. IN EXIST. WALL OR PARTITION WITH NEW CONSTR.-SEE REMODELING PLAN /COORD.

